



NOTES:

1. CONTRACTOR SHALL SUPPLY DISTRICT WITH 4'-5' VALVE ACTUATOR HANDLE TO TURN VALVE.
2. ALL HDPE JOINTS SHALL BE FUSED.
3. TRACE WIRE SHALL BE CONTINUOUS 8 GAUGE SOLID AND COATED COPPER WITH 2 FEET COILED IN BOX.
4. RISER SHALL BE SAME SIZE AS FORCEMAIN.

WEST BAY SANITARY DISTRICT		
CLEANOUT 2"-3" FORCEMAIN (STEP AND GRINDER PUMP SYSTEMS)		
APPROVED BY:		
/s/ - PHIL SCOTT	06-24-15	11
DISTRICT MANAGER	DATE:	