

- 1. CONTRACTOR SHALL SUPPLY DISTRICT WITH 4'-5' VALVE ACTUATOR HANDLE TO TURN VALVE.
- 2. ALL HDPE JOINTS SHALL BE FUSED.
- 3. TRACE WIRE SHALL BE CONTINUOUS 8 GAUGE SOLID AND COATED COPPER WITH 2 FEET COILED IN BOX.
- 4. RISER SHALL BE SAME SIZE AS FORCEMAIN.

WEST BAY SANITARY DISTRICT		
CLEANOUT STATION 2"-3" FORCEMAIN (STEP AND GRINDER PUMP SYSTEMS)		
APPROVED BY:		
/S/ - SERGIO RAMIREZ	06-28-23	11
GENERAL MANAGER	DATE:	